

AD-A074 358

NEW JERSEY DEPT OF ENVIRONMENTAL PROTECTION TRENTON

F/G 13/2

NATIONAL DAM SAFETY PROGRAM. BIRCHWOOD LAKE DAM (NJ 00168), PAS--ETC(U)

AUG 79 W A GUINAN

DACW61-79-C-0011

NL

UNCLASSIFIED

1 OF 1
AD
A074358



END
DATE
FILMED
10-79
DDC

①

PASSAIC RIVER BASIN
TROY BROOK, MORRIS COUNTY
NEW JERSEY

LEVEL II

BIRCHWOOD LAKE DAM

NJ 00168

PHASE 1 INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM



New Jersey Dept.
of Environmental
Protection, Trenton
410 891

DDC FILE COPY

DEPARTMENT OF THE ARMY

Philadelphia District
Corps of Engineers
Philadelphia, Pennsylvania

DDC

SEP 27 1979

August, 1979

D

79 09 24 096

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER NJ00168	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Phase I Inspection Report National Dam Safety Program Birchwood Lake Dam Morris County, NJ		5. TYPE OF REPORT & PERIOD COVERED 9 FINAL rept.
7. AUTHOR(s) Guinan, Warren A. P.E.		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS Anderson-Nichols 6 Louden Rd. Concord, NH 03301		8. CONTRACT OR GRANT NUMBER(s) DACW61-79-C-0011
11. CONTROLLING OFFICE NAME AND ADDRESS U.S. Army Engineer District, Philadelphia Custom House, 2d & Chestnut Streets Philadelphia, Pennsylvania 19106		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) 12 81 p.		12. REPORT DATE August 1979
		13. NUMBER OF PAGES 45
		15. SECURITY CLASS. (of this report) Unclassified
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited.		
17. DISTRIBUTION STATEMENT (of this Report) National Dam Safety Program. Birchwood Lake Dam (NJ 00168), Passaic River Basin, Troy Brook, Morris County, New Jersey. Phase 1 Inspection Report.		
18. SUPPLEMENTARY NOTES Copies are obtainable from National Technical Information Service, Springfield, Virginia, 22151.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Spillway Seepage Flows Birchwood Lake Dam, N.J. Slope National Dam Safety Program Report Embankment Structural Analysis		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report cites results of a technical investigation as to the dam's adequacy. The inspection and evaluation of the dam is as prescribed by the National Dam Inspection Act, Public Law 92-367. The technical investigation includes visual inspection, review of available design and construction records, and preliminary structural and hydraulic and hydrologic calculations, as applicable. An assessment of the dam's general condition is included in the report.		

DD FORM 1473
1 JAN 73

EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

410 891

Law

NOTICE

THIS DOCUMENT HAS BEEN REPRODUCED
FROM THE BEST COPY FURNISHED US BY
THE SPONSORING AGENCY. ALTHOUGH IT
IS RECOGNIZED THAT CERTAIN PORTIONS
ARE ILLEGIBLE, IT IS BEING RELEASED
IN THE INTEREST OF MAKING AVAILABLE
AS MUCH INFORMATION AS POSSIBLE.



DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
CUSTOM HOUSE - 2 D & CHESTNUT STREETS
PHILADELPHIA, PENNSYLVANIA 19106

IN REPLY REFER TO

NAPEN-D

17 SEP 1979

Honorable Brendan T. Byrne
Governor of New Jersey
Trenton, NJ 08621

Dear Governor Byrne:

Inclosed is the Phase I Inspection Report for Birchwood Lake Dam in Morris County, New Jersey which has been prepared under authorization of the Dam Inspection Act, Public Law 92-367. A brief assessment of the dam's condition is given in the front of the report.

Based on visual inspection, available records, calculations and past operational performance, Birchwood Lake Dam, a high hazard potential structure, is judged to be in poor overall condition. Also, the spillway is considered seriously inadequate since 19 percent of the Probable Maximum Flood (PMF) would overtop the dam. The seriously inadequate spillway is assessed as an UNSAFE, non-emergency condition, until more detailed studies prove otherwise or corrective measures are completed. The classification of UNSAFE applied to a dam because of a seriously inadequate spillway is not meant to indicate the same degree of emergency as would be associated with an UNSAFE classification applied for a structural deficiency. It does mean, however, that based on an initial screening, and preliminary computations, there appears to be a serious deficiency in spillway capacity so that if a severe storm were to occur, overtopping and failure of the dam would take place, significantly increasing the hazard of loss of life downstream from the dam. To insure adequacy of the structure, the following actions, as a minimum, are recommended:

a. The spillway's adequacy should be determined by a qualified professional consultant engaged by the owner using more sophisticated methods, procedures, and studies within six months from the date of approval of this report. Any remedial measures necessary to insure the adequacy of the spillway and to prevent overtopping should be initiated within calendar year 1980. In the interim, a detailed emergency operation plan and warning system should be promptly developed. Also, during periods of unusually heavy precipitation, around the clock surveillance should be provided.

NAPEN-D

Honorable Brendan T. Byrne

b. Within six months from the date of approval of this report, engineering studies and analyses should be performed to:

(1) Investigate the seepage at the downstream toe and design and implement appropriate remedial measures.

(2) Specify and supervise procedures for removal of the trees, their roots, and brush on the downstream slope of the dam.

(3) Specify and implement appropriate remedial measures for the erosion on the downstream slope of the dam.

(4) Design and install adequate means to drain the reservoir in case of emergency.

c. Within thirty days from the date of approval of this report, a program should be initiated to check the condition of the dam periodically and monitor the seepage until remedial measures are effected.

d. Within three months from the date of approval of this report, trespassing on the downstream face of the dam should be controlled.

e. The following remedial actions should be completed within one year from the date of approval of this report:

(1) Establish a ground cover and maintain the dam, free of brush.

(2) Engage a professional engineer qualified in the design and inspection of dams to make a comprehensive technical inspection of the dam once every two years.

f. The legal implications of directing large flows out of the watershed during periods of high flow should be investigated within six months from the date of approval of this report.

A copy of the report is being furnished to Mr. Dirk C. Hofman, New Jersey Department of Environmental Protection, the designated State Office contact for this program. Within five days of the date of this letter, a copy will also be sent to Congressman James A. Courter of the Thirteenth District. Under the provision of the Freedom of Information Act, the inspection report will be subject to release by this office, upon request, five days after the date of this letter.

Additional copies of this report may be obtained from the National Technical Information Services (NTIS), Springfield, Virginia 22161 at a reasonable cost. Please allow four to six weeks from the date of this letter for NTIS to have copies of the report available.


NAPEN-D

Honorable Brendan T. Byrne

An important aspect of the Dam Safety Program will be the implementation of the recommendations made as a result of the inspection. We accordingly request that we be advised of proposed actions taken by the State to implement our recommendations.

Sincerely,

1 Incl
As stated


JOEL T. CALLAHAN
Lieutenant Colonel, Corps of Engineers
Acting District Engineer

Copies furnished:
Dirk C. Hofman, P.E., Deputy Director
Division of Water Resources
N.J. Dept. of Environmental Protection
P.O. Box CN029
Trenton, NJ 08625

John O'Dowd, Acting Chief
Bureau of Flood Plain Management
Division of Water Resources
N.J. Dept. of Environmental Protection
P.O. Box CN029
Trenton, NJ 08625

Accession For	
NTIS GRA&I	<input checked="checked" type="checkbox"/>
DDC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By _____	
Distribution/ _____	
Availability Codes	
Dist	Availand/or special
A	

DDC
RECEIVED
SEP 27 1979
D

BIRCHWOOD LAKE DAM (NJ00168)

CORPS OF ENGINEERS ASSESSMENT OF GENERAL CONDITIONS

This dam was inspected on 16 May 1979 by Anderson-Nichols and Company, Inc. under contract to the State of New Jersey. The State, under agreement with the U.S. Army Engineer District, Philadelphia, had this inspection performed in accordance with the National Dam Inspection Act, Public Law 92-367.

Birchwood Lake Dam, a high hazard potential structure, is judged to be in poor overall condition. Also, the spillway is considered seriously inadequate since 19 percent of the Probable Maximum Flood (PMF) would overtop the dam. The seriously inadequate spillway is assessed as an UNSAFE, non-emergency condition, until more detailed studies prove otherwise or corrective measures are completed. The classification of UNSAFE applied to a dam because of a seriously inadequate spillway is not meant to indicate the same degree of emergency as would be associated with an UNSAFE classification applied for a structural deficiency. It does mean, however, that based on an initial screening, and preliminary computations, there appears to be a serious deficiency in spillway capacity so that if a severe storm were to occur, overtopping and failure of the dam would take place, significantly increasing the hazard of loss of life downstream from the dam. To insure adequacy of the structure, the following actions, as a minimum, are recommended.

a. The spillway's adequacy should be determined by a qualified professional consultant engaged by the owner using more sophisticated methods, procedures, and studies within six months from the date of approval of this report. Any remedial measures necessary to insure the adequacy of the spillway and to prevent overtopping should be initiated within calendar year 1980. In the interim, a detailed emergency operation plan and warning system should be promptly developed. Also, during periods of unusually heavy precipitation, around the clock surveillance should be provided.

b. Within six months from the date of approval of this report, engineering studies and analyses should be performed to:

- (1) Investigate the seepage at the downstream toe and design and implement appropriate remedial measures.
- (2) Specify and supervise procedures for removal of the trees, their roots, and brush on the downstream slope of the dam.
- (3) Specify and implement appropriate remedial measures for the erosion on the downstream slope of the dam.
- (4) Design and install adequate means to drain the reservoir in case of emergency.

c. Within thirty days from the date of approval of this report, a program should be initiated to check the condition of the dam periodically and monitor the seepage until remedial measures are effected.

d. Within three months from the date of approval of this report, trespassing on the downstream face of the dam should be controlled.

e. The following remedial actions should be completed within one year from the date of approval of this report:

(1) Establish a ground cover and maintain the dam, free of brush.

(2) Engage a professional engineer qualified in the design and inspection of dams to make a comprehensive technical inspection of the dam once every two years.

f. The legal implications of directing large flows out of the watershed during periods of high flow should be investigated within six months from the date of approval of this report.

APPROVED:

James G. Ton
JAMES G. TON

Colonel, Corps of Engineers

District Engineer

DATE:

14 September 1975



DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
CUSTOM HOUSE-2 D & CHESTNUT STREETS
PHILADELPHIA, PENNSYLVANIA 19106

IN REPLY REFER TO

NAPEN-D

13 SEP 1979

Honorable Brendan T. Byrne
Governor of New Jersey
Trenton, NJ 08621

Dear Governor Byrne:

This is in reference to our ongoing National Program for Inspection of Non-Federal Dams within the State of New Jersey. Birchwood Lake Dam (Federal I.D. No. NJ00168), a high hazard potential structure has recently been inspected. The dam is owned by the Borough of Mountain Lakes and is located on Troy Brook in Mountain Lakes.

Using Corps of Engineers' screening criteria, it has been determined that the dam's spillway is seriously inadequate since approximately 19 percent of the Probable Maximum Flood would overtop the dam. The seriously inadequate spillway is assessed as an UNSAFE, non-emergency condition, until more detailed studies prove otherwise, or corrective measures are completed. The classification of UNSAFE applied to a dam because of a seriously inadequate spillway is not meant to indicate the same degree of emergency as would be associated with an UNSAFE unclassification applied for a structural deficiency. It does mean, however, that based on an initial screening and preliminary computations, there appears to be a serious deficiency in spillway capacity so that if a severe storm were to occur, overtopping and failure of the dam could take place, significantly increasing the hazard potential to loss of life downstream from the dam. As a result of this UNSAFE determination, it is recommended that the dam's owner take the following measures within 30 days of the date of this letter:

- a. Engage the services of a qualified professional consultant to more accurately determine the spillway adequacy by using more detailed and sophisticated hydrologic and hydraulic analyses, and to recommend any remedial measures required to prevent overtopping of the dam.


NAPEN-D

Honorable Brendan T. Byrne

b. In the interim, a detailed emergency operation plan and downstream warning system should be developed. Also, round-the-clock surveillance should be provided during periods of unusually heavy precipitation.

A final report on this Phase I Inspection will be forwarded to you within two months.

Sincerely,

 LTC
JAMES G. TON
Colonel, Corps of Engineers
District Engineer

Copies Furnished:

Dirk C. Hofman, Actg. Deputy Director
Division of Water Resources
N.J. Dept. of Environmental Protection
P.O. Box CN029
Trenton, NJ 08625

John O'Dowd, Acting Chief
Bureau of Flood Plain Management
Division of Water Resources
N.J. Dept. of Environmental Protection
P.O. Box CN029
Trenton, NJ 08625

UNSAFE DAM
NATIONAL PROGRAM OF INSPECTION OF DAMS

a. NAME: Birchwood Lake Dam b. ID NO.: NJ00168 c. LOCATION State: New Jersey County: Morris
d. HEIGHT: 20 feet. e. MAXIMUM IMPOUNDMENT CAPACITY: 105 ac ft. River or Stream: Troy Brook
Nearest D/S City or Town: Mountain Lakes

f. TYPE: Earthfill.

g. OWNER: Borough of Mountain Lakes.

h. DATE GOVERNOR NOTIFIED OF UNSAFE CONDITIONS: 13 Sep 79.

i. CONDITION OF DAM RESULTING IN UNSAFE ASSESSMENT Preliminary report calculations indicate 19% of PMF would overtop the dam.

l. URGENCY CATEGORY: UNSAFE, Non-Emergency.

m. EMERGENCY ACTIONS TAKEN:

Gov. notified of this condition by District Engineer's letter of 13 Sep 79.

j. DESCRIPTION OF DANGER INVOLVED:

Overtopping and failure of the dam would significantly increase hazard potential to loss of life and property downstream of dam.

h. REMEDIAL ACTIONS TAKEN:

N.J.D.E.P. will notify dam's owner upon receipt of our letter.

k. RECOMMENDATIONS GIVEN TO GOVERNOR:

Within 30 days of date of District Engineer letter the owner do the following:

a. Engage the services of a qualified professional consultant to more accurately determine the spillway adequacy by using more detailed and sophisticated hydrologic and hydraulic analyses, and to recommend any remedial measures required to prevent overtopping of the dam.

b. In the interim, a detailed emergency operation plan and downstream warning system should be developed. Also, around-the-clock surveillance should be provided during periods of unusually heavy precipitation.

o. REMARKS: Final report, to be issued within six weeks, will have WHITE cover.

W.H. Zink
W. H. ZINK, Coordinator
Dam Inspection Program
U.S.A.E.D., Philadelphia

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

Name of Dam: Birchwood Lake Dam
ID Number: ID No. NJ00168
State Located: New Jersey
County Located: Morris
Stream: Troy Brook
River Basin: Passaic
Date of Inspection: May 16, 1979

ASSESSMENT OF GENERAL CONDITIONS

Birchwood Lake Dam is an old dam of undetermined age and is in poor overall condition. It is small in size and is classified as High Hazard. A large rust colored seepage, estimated as 15 gpm, was observed at the toe of the dam. Trees and brush are growing on the downstream slope of the dam. The concrete junction box on the spillway discharge pipe is leaking and there is an undermining and erosion around the broken end of the discharge pipe. Erosion caused by trespassing is present on the downstream face of the dam.

The lake and dam are capable of passing 18 percent of the PMF without causing the dam to overtop. Dam failure resulting from overtopping would significantly increase the hazard to loss of life downstream over the non-failure condition. Thus the spillway is judged to be seriously inadequate.

We recommend that the owner, in the near future, retain the services of a professional engineer, qualified in the design and inspection of dams, to accomplish the following: further evaluate the hydrology and hydraulic capacity of the watershed, reservoir, dam and spillway; and determine, design and implement mitigating measures determined necessary to provide the dam with the ability to withstand high discharges; investigate the seepage at the downstream toe of the dam and design and supervise the implementation of appropriate remedial measures; specify and supervise procedures for removing trees, their roots, and brush from the downstream slope of the dam; specify and implement appropriate remedial measures for the erosion on the downstream slope of the dam; and, in the future, design and install adequate means to drain the reservoir in case of emergency.

We further recommend that as a part of operating and maintenance procedures, the owner check the condition of the dam once each month and monitor the seepage until remedial measures are effected. This should be started immediately. Control trespassing on the downstream face of the dam. This should be started very soon. Establish a ground cover and maintain the

dam free of brush. This should be done in the future. Establish a surveillance program for use during and immediately following periods of heavy rainfall, and also a warning program to follow in case of floodflow conditions or imminent dam failure. This should be done soon. Engage a professional engineer, qualified in the design and inspection of dams, to make a comprehensive technical inspection of the dam once every two years. This should be started in the future. Investigate the legal implications of directing large flows out of watershed during periods of high flows. This should be done in the future.

Warren A. Guinan

Warren A. Guinan, P.E.
Project Manager
N.J. No. 16848



OVERVIEW
BIRCHWOOD LAKE DAM

16 MAY 1979

CONTENTS
PHASE I INSPECTION REPORT
BIRCHWOOD LAKE DAM N.J. NO. 25-70 AND FED ID NO. NJ00168

	<u>Page</u>
PREFACE	
SECTION 1 PROJECT INFORMATION	
1.1 <u>General</u>	1
1.2 <u>Project Description</u>	1
1.3 <u>Pertinent Data</u>	2
SECTION 2 ENGINEERING DATA	
2.1 <u>Design</u>	5
2.2 <u>Construction</u>	5
2.3 <u>Operation</u>	5
2.4 <u>Evaluation</u>	5
SECTION 3 VISUAL INSPECTION	6
SECTION 4 OPERATIONAL PROCEDURES	
4.1 <u>Procedures</u>	7
4.2 <u>Maintenance of Dam</u>	7
4.3 <u>Maintenance of Operating Facilities</u>	7
4.4 <u>Warning System</u>	7
4.5 <u>Evaluation of Operational Adequacy</u>	7
SECTION 5 HYDRAULIC/HYDROLOGIC	8
SECTION 6 STRUCTURAL STABILITY	10
SECTION 7 ASSESSMENT, RECOMMENDATIONS/REMEDIAL MEASURES	
7.1 <u>Assessment</u>	11
7.2 <u>Recommendations/Remedial Measures</u>	11
FIGURES	
1. Location Map	
2. Essential Project Features	
APPENDICES	
1. Check List, Visual Inspection	
2. Photographs	
3. Hydrologic Computations	
4. References	

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In review this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test Flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. The test flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY INSPECTION PROGRAM
BIRCHWOOD LAKE DAM
U.S. #NJ00168 and N.J. #25-70

SECTION 1 PROJECT INFORMATION

1.1 General

a. Authority. Authority to perform the Phase I Safety Inspection of Birchwood Lake Dam was received from the State of New Jersey, Department of Environmental Protection, Division of Water Resources by letter dated 4 April 1979 under Contract No. FPM-39 dated 28 June 1978. This Authority was given pursuant to the National Dam Inspection Act, Public Law 92-367 and by agreement between the State and the U.S. Army Engineers District, Philadelphia. The inspection discussed herein was performed by Anderson-Nichols & Company, Inc. on 16 May 1979.

b. Purpose. The purpose of the Phase I Investigation is to develop an assessment of the general conditions with respect to the safety of Birchwood Lake Dam and appurtenances based upon available data and visual inspection, and determine any need for emergency measures and conclude if additional studies, investigations and analyses are necessary and warranted.

1.2 Project Description

a. Description of Dam and Appurtenances. Birchwood Lake Dam is an old (construction date unknown) earthfill dam, which is approximately 160 feet long, has a structural height of 20.3 feet and a hydraulic height of 18.8 feet. The topwidth of the dam is approximately 30 feet. The upstream face is of undetermined slope. The downstream face is 2H:1V. A concrete inlet box with a 2.5-foot high by 2.0-foot wide opening, gated with wood stoplogs, is located in the center of the dam. Concrete wingwalls six feet long and at 60 degree angles contract the flow to the inlet box. The box is covered with a steel plate which determines the minimum elevation of the dam (552.7 feet MSL). With 1.0 foot height of stoplogs in place at the time of the inspection the box opening was limited to 1.5 feet by 2 feet. From the inlet box, flow is discharged through 10-inch diameter AC pipe down the face of the dam to a concrete junction box, located about half way down the slope. From the junction box another 10-inch AC pipe carries the flow to Crystal Lake. The reservoir is surrounded by park land. The watershed above the reservoir is gently to steeply sloping and generally wooded. There is a natural low saddle at the north end of the reservoir which has a minimum elevation of 551.6 feet MSL, (cross-section included in Appendix 3) and will act as an emergency spillway during high flows. Flow over this saddle leaves the Troy Brook

watershed flowing through a sparsely populated area to the Rockaway River. A second natural low saddle is located on the southeast bank of reservoir north of the spillway and has a minimum elevation of 553.5 feet MSL. (Cross-section included in Appendix 3.) Flow over this saddle will be discharged directly to Crystal Lake. Essential features of the dam are shown in Figure 2.

b. Location. The dam is located in the Borough of Mountain Lakes, Morris County, New Jersey, at the headwaters of Troy Brook. It has coordinates north latitude $40^{\circ} 53.6'$ and west longitude $74^{\circ} 27.1'$. A location map is shown in Figure 1.

c. Size Classification. Birchwood Lake Dam is classified as being small in size, as defined in the Recommended Guidelines for Safety Inspection of Dams, on the basis of its structural height of 20.3 feet, which is less than 40 feet, and its storage volume of 107 acre-feet which is less than 1000 acre-feet, but more than 50 acre-feet.

d. Hazard Classification. Visual inspection of the downstream area indicates that a breach of Birchwood Lake Dam would likely cause breaching of Crystal Lake and subsequent breaching of Sunset Lake Dam. Approximately 10 residences are located immediately below Sunset Lake Dam, some with first floor elevations below the normal pool level of the lake. A breach of Birchwood Lake Dam, would, therefore, likely cause excessive property damage and put up to 20 lives in jeopardy. Birchwood Lake Dam is thus classified as High Hazard.

e. Ownership. Birchwood Lake Dam is owned by the Borough of Mountain Lakes. Mr. Carl Danser, Superintendent of Public Works (334-3131) was contacted for information and was present during the inspection.

f. Purpose of Dam. The dam was originally constructed to impound an ice pond. Currently the reservoir and shores are heavily used for recreation.

g. Design and Construction History. No plans, hydraulic or hydrologic data for the original construction were disclosed. Reference data on file with the NJDEP dated 7 November 1928 indicates that the dam is old and was constructed by Mountain Ice Company. This is the oldest disclosed record regarding construction history of the dam.

h. Normal Operational Procedures. No formal operating procedures were disclosed.

1.3 Pertinent Data

a. Drainage Area - 0.2 square mile

b. Discharge at Damsite (cfs)

Maximum flood at damsite - unknown

Gated spillway capacity at pool elevation with stoplogs in place (as during inspection) - 0.5+

Gated spillway capacity at maximum pool (top of dam) elevation with stoplogs removed - 6 (controlled by pipe capacity)

Ungated spillway (north saddle) capacity at maximum pool elevation - 172

Total spillway capacity at maximum pool elevation - 178

c. Elevation (ft. above MSL)

Top dam - 552.7

Natural low saddle at north end of the lake - 551.6

Maximum pool - design surcharge ($\frac{1}{2}$ PMF) - 553.5

Recreation pool - (at the time of inspection) - 551.1

Spillway crest (stoplogs) - 551.0

Streambed at centerline of dam (Crystal Lake) - 533.9

Maximum tailwater - (estimated) - 537.7

d. Reservoir

Length of maximum pool - 1750 feet

Length of recreation pool - 1700 feet

e. Storage (acre-feet)

Recreation pool - 89

Design surcharge - 117

Top of dam - 106

Crest of north low saddle - 97.9

f. Reservoir Surface (acres)

Top of Dam - 11.2

Recreation pool - 11

Spillway crest - 11

g. Dam

Type - earthfill

Length - 160+ feet

Height - hydraulic - 18.8 feet
 structural - 20.3 feet

Topwidth - 30+ feet

Side slopes - upstream - not visible
 - downstream - 2H:1V

Zoning - unknown

Impervious core - unknown

Cutoff - unknown

Grout curtain - unknown

h. Spillway

Type - stoplog

Length of weir - 2.0 feet

Crest elevation - sill 550.0
 - with stoplogs in place (as during
 inspection) 551.0

Gates - rough cut 2 x 4-inch by 2-foot long stoplogs.

U/S Channel - Birchwood Lake

D/S Channel - Crystal Lake

SECTION 2
ENGINEERING DATA

2.1 Design

No original engineering design data or plans were disclosed.

2.2 Construction

No original construction data were disclosed. Reconstruction of stone wall along south end of reservoir adjacent to spillway inlet was in progress at the time of inspection.

2.3 Operation

No engineering operational data were disclosed.

2.4 Evaluation

a. Availability. A search of New Jersey Department of Environmental Protection files and contact with community officials revealed a very limited amount of information.

b. Adequacy. The information available was such that the evaluation of this dam was based solely on visual observations.

SECTION 3
VISUAL INSPECTION

3.1 Findings

a. Dam. A large seepage is discharging from the downstream toe of the dam in the vicinity of the spillway discharge pipe. Flow was estimated at 15 gpm. Extensive trespassing and erosion on the downstream slope of the dam, especially in the vicinity of the spillway discharge pipe was observed. There is no riprap protection on the upstream slope. A new stone masonry retaining wall was being constructed in a shallow trench on the upstream edge of the crest of the dam at the time of the inspection. Brush and trees up to 2 feet in diameter are growing on the downstream slope of the dam.

b. Appurtenant Structures. The spillway discharge pipe has been exposed and partially undermined as a result of erosion on the downstream slope, and the discharge end of the pipe is broken. There is a leak in the concrete junction box which is located on the spillway discharge line at about mid-height of the downstream slope.

c. Reservoir Area. The reservoir is surrounded by park land and there is a bathhouse on the shore of the reservoir near the right abutment. The watershed above the reservoir is gently to steeply sloping and generally wooded. Slopes adjacent to the channel appear to be stable. No evidence of significant sedimentation in the reservoir was observed.

d. Downstream Channel. The spillway outlet pipe discharges directly into Crystal Lake; there is no downstream channel per se.

SECTION 4
OPERATIONAL PROCEDURES

4.1 Procedures

No formal operating procedures were disclosed.

4.2 Maintenance of Dam

No formal maintenance procedures for the dam were disclosed.

4.3 Maintenance of Operating Facilities

No formal maintenance procedures for the operating facilities were disclosed.

4.4 Warning System

No description of any warning system was disclosed.

4.5 Evaluation of Operational Adequacy

Because of the lack of operation and maintenance procedures the remedial measures described in Section 7.2 c. should be implemented as prescribed.

SECTION 5
HYDROLOGIC/HYDRAULIC

5.1 Evaluation of Features

a. Design Data. No hydrologic or hydraulic design data were disclosed.

b. Experience Data. Reference data on file with NJDEP dated 7 November 1928 indicates that the dam was overtopped during 1928, and that damage to the dam has been repaired. No indication of downstream damage was given. No other experience data were disclosed.

c. Visual Observation. No visible evidence of damage to the structure caused by overtopping was observed. A large rust colored seepage estimated at 15 gpm was discharging from the downstream toe of the dam in the vicinity of the spillway discharge pipe. At the time of inspection about 1 inch of water was flowing over the stoplogs.

d. Overtopping Potential. The hydraulic/hydrologic evaluation for Birchwood Lake Dam is based on a Spillway Design Flood (SDF) equal to one-half the Probable Maximum Flood (PMF) in accordance with the range of test floods given in the evaluation guidelines for dams classified as high hazard and small in size. The PMF has been determined by application of the SCS dimensionless unit hydrograph procedure to a 6-hour PMP storm of 25.5 inches. Hydrologic computations are given in Appendix 3. The routed half-PMF peak discharge for the subject watershed is 753 cfs. Approximately 215 cfs of this discharge passes over the dam and through the spillway into Crystal Lake. The remaining 538 cfs passes through the low saddle at the north end of the lake and flows through a sparsely populated area into the Rockaway River.

The minimum elevation of the dam allows 2.7 feet of depth above the stoplogs before overtopping begins. Under this head the spillway discharge pipe capacity is 6 cfs. Under this same head the natural low saddle at the north end of the reservoir (minimum elevation 551.6 MSL) is discharging approximately 172 cfs toward the Rockaway River.

Routing calculations indicate that Birchwood Lake Dam will be overtopped for more than 2 hours to a maximum depth of 0.8 feet under half-PMF conditions. It is estimated that the spillway can pass 18 percent of the PMF without overtopping the dam. The spillway can pass less than 50 percent

of the PMF, and the dam is classified as High Hazard. Dam failure resulting from overtopping would significantly increase the hazard to loss of life downstream from that which would exist just before overtopping failure, therefore the spillway for Birchwood Lake Dam is judged to be seriously inadequate.

SECTION 6 STRUCTURAL STABILITY

6.1 Evaluation of Structural Stability

a. Visual Observations. The large seepage at the downstream toe of the dam, if not corrected, could lead to future instability of the dam. Trespassing, if not controlled, and erosion, if not repaired and controlled, could also lead to future instability of the dam. Trees growing on the embankment may blow over and pull out their roots, or, if they die or are cut, their roots may rot. In either case, serious erosion or seepage problems may result. The leak in the concrete junction box on the spillway discharge pipe, the broken end of the discharge pipe, and the undermining and erosion around the discharge pipe could all lead to further damage and plugging of the spillway discharge pipe if not corrected.

b. Design and Construction Data. No design or construction data pertinent to the structural stability of the dam were disclosed.

c. Operating Records. No operating records pertinent to the structural stability of the dam were disclosed.

d. Post-Construction Changes. No records pertinent to post-construction changes were disclosed.

e. Seismic Stability. Birchwood Lake Dam is in Seismic Zone 1 and in accordance with the recommended Phase I guidelines does not warrant seismic analysis.

SECTION 7
ASSESSMENT, RECOMMENDATIONS/REMEDIAL MEASURES

7.1 Dam Assessment

a. Condition. Birchwood Lake Dam is an old dam of undetermined age and is in poor overall condition.

b. Adequacy of Information. The information available is such that the assessment of the dam must be based solely on the results of the visual inspection.

c. Urgency. The recommendations made in Section 7.2 a. and the operating and maintenance procedures in 7.2 c. should be implemented by the owner as prescribed below.

d. Necessity for Additional Data/Evaluation. The information available from the visual inspection is adequate to identify the potential problems that are listed in Sections 5 and 6. These problems require the attention of a professional engineer qualified in the design and inspection of dams who will have to make additional engineering studies to design or specify remedial measures. If left unattended, the problems could lead to instability of the structure. Because the spillway is judged to be seriously inadequate, additional evaluation of the hydrology and the hydraulics of the dam, using more detailed methods is necessary.

7.2 Recommendations/Remedial Measures

a. Recommendations. The owner should retain the services of a professional engineer qualified in the design and inspection of dams to accomplish the following in the near future:

(1) Conduct a more detailed investigation of the hydrology and hydraulics of the watershed, reservoir, dam and spillway; and determine, design, and implement the necessary mitigating measures to provide the dam with the ability to withstand high discharges.

(2) Investigate the seepage at the downstream toe and design and implement appropriate remedial measures.

(3) Specify and supervise procedures for removal of the trees, their roots, and brush on the downstream slope of the dam.

(4) Specify and implement appropriate remedial measures for the erosion on the downstream slope of the dam.

(5) Design and install adequate means to drain the reservoir in case of emergency.

b. Operating and Maintenance Procedures. The owner should:

(1) Check the condition of the dam periodically and monitor the seepage until remedial measures are effected. This should be started immediately.

(2) Control trespassing on the downstream face of the dam. This should be started very soon.

(3) Establish a ground cover and maintain the dam, free of brush after completion of a.(3) above in the future.


(4) Establish a surveillance program for use during and immediately following periods of heavy rainfall, and also a warning program to follow in case of floodflow conditions or imminent dam failure. This should be done soon.

(5) Engage a professional engineer qualified in the design and inspection of dams to make a comprehensive technical inspection of the dam once every two years. This should be started in the future.

(6) Investigate the legal implications of directing large flows out of the watershed during periods of high flow.




SCALE IN MILES




MAP BASED ON STATE OF NEW JERSEY
OFFICIAL HIGHWAY MAP AND GUIDE.

Anderson-Nichols & Co., Inc.		U.S. ARMY ENGINEER DIST. PHILADELPHIA	
BOSTON		CORPS OF ENGINEERS	
MASSACHUSETTS		PHILADELPHIA, PA.	
NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS			
BIRCHWOOD LAKE DAM			
LOCATION MAP			
TROY BROOK		NEW JERSEY	
		SCALE: SEE BAR SCALE	
		DATE: AUGUST 1979	

FIGURE 1




SECTION A-A



ELEVATION B-B

CRYSTAL LAKE



PLAN

Data from field inspection May 16, 1979

Anderson - Nichols & Co., Inc.		U.S. ARMY ENGINEER DIST. PHILADELPHIA	
BOSTON		CORPS OF ENGINEERS	
MASSACHUSETTS		PHILADELPHIA, PA	
NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS			
BIRCHWOOD LAKE DAM			
TROY BROOK		NEW JERSEY	
		SCALE: NOT TO SCALE	
		DATE: AUGUST, 1979	

FIGURE 2

APPENDIX 1

CHECKLIST

VISUAL INSPECTION

BIRCHWOOD LAKE DAM

Check List
Visual Inspection
Phase 1

Name Dam Birchwood Lake Dam County Morris State New Jersey Coordinators NJDEP
 Date(s) Inspection May 16, 1979 Weather Sunny Temperature 65°
 Pool Elevation at Time of Inspection 551.1 MSL Tailwater at Time of Inspection 533.9 MSL

Inspection Personnel:

<u>Warren Guinan</u>	<u>Ronald Hirschfeld</u>
<u>Steve Gilman</u>	<u></u>
<u>David Deane</u>	<u></u>

Gilman & Hirschfeld Recorder

Carl Danser, Superintendent of Public Works for the Borough of Mountain Lakes was present during inspection.

EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS	None apparent.	
UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE	None apparent.	
SLOUGHING OR EROSION OF EMBANKMENT AND ABUTMENT SLOPES	Considerable erosion of downstream slope at location of spillway discharge pipe, crushed rock has been dumped next to pipe, also evidence of trespassing and erosion of downstream slope to right of spillway.	Repair spillway discharge pipe. Provide appropriate slope protection.
VERTICAL AND HORIZONTAL ALIGNMENT OF THE CREST	Good.	
RIPRAP FAILURES	No riprap.	Provide appropriate slope protection.

EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
RAILINGS		
JUNCTION OF EMBANKMENT AND ABUTMENT, SPILLWAY AND DAM	No apparent problems.	
ANY NOTICEABLE SEEPAGE	Major seepage to left of spillway discharge pipe and to right of discharge pipe. Estimated flow - 15 gpm.	Investigate seepage; design and implement appropriate control measures.
STAFF GAGE AND RECORDER	None apparent.	
DRAINS	None apparent.	

UNGATED SPILLWAY - Northeast Saddle

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE WEIR	None.	
APPROACH CHANNEL	Wide and generally unobstructed. Many water plants in north end of reservoir.	
DISCHARGE CHANNEL	Wide, forested, parabolic shape channel with very gentle slope leading to Rockaway River tributary	
BRIDGE AND PIERS OVER SPILLWAY	None.	

GATED SPILLWAY - 10-inch Pipe and Stoplog Entrance

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE SILL 10" concrete walls with 10' @ u/s face of wingwalls	Concrete - Good condition only surface laitance eroded. Steel plate on top - good condition - surface rust only. 10" AC outlet pipe-good condition. Concrete block - pipe structure - block & joints weathered - leakage around outlet pipe - steel top plate rusted	
APPROACH CHANNEL	Wide. Three docks extend part way across channel.	
DISCHARGE CHANNEL	Spillway pipe discharges directly into Crystal Lake.	
BRIDGE AND PIERS	None.	
GATES AND OPERATION EQUIPMENT	Wood stoplogs - weathered and deteriorated	

RESERVOIR

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SLOPES	Gentle, wooded.	
SEDIMENTATION	No evidence of significant sedimentation.	

DOWNSTREAM CHANNEL

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONDITION (OBSTRUCTIONS, DEBRIS, ETC.)	Crystal Lake is at toe of downstream slope.	
SLOPES	See above.	
APPROXIMATE NO. OF HOMES AND POPULATION	10 residences, estimated population of 20, below Sunset Lake Dam. Several have first floor elevations below Sunset Lake normal water level.	

CHECK LIST
ENGINEERING DATA
DESIGN, CONSTRUCTION, OPERATION

ITEM	REMARKS
PLAN OF DAM	No original plans were disclosed. Plans for this report were developed from visual inspection.
REGIONAL VICINITY MAP	Prepared for this report.
CONSTRUCTION HISTORY	None disclosed.
TYPICAL SECTIONS OF DAM	Prepared for this report from visual inspection.
HYDROLOGIC/HYDRAULIC DATA	None disclosed.
OUTLETS - PLAN	None disclosed.
- DETAILS	None disclosed.
- CONSTRAINTS	None disclosed.
- DISCHARGE RATINGS	None disclosed.
RAINFALL/RESERVOIR RECORDS	None disclosed.

ITEM	REMARKS
DESIGN REPORTS	None disclosed.
GEOLOGY REPORTS	None disclosed.
DESIGN COMPUTATIONS HYDROLOGY & HYDRAULICS DAM STABILITY SEEPAGE STUDIES	None disclosed.
MATERIALS INVESTIGATIONS BORING RECORDS LABORATORY FIELD	None disclosed.
POST-CONSTRUCTION SURVEYS OF DAM	None disclosed.
BORROW SOURCES	Unknown.

ITEM	REMARKS
MONITORING SERVICES	Unknown.
MODIFICATIONS	None disclosed.
HIGH POOL RECORDS	None disclosed.
POST CONSTRUCTION ENGINEERING STUDIES AND REPORTS	None disclosed.
PRIOR ACCIDENTS OR FAILURE OF DAM DESCRIPTION REPORTS	None disclosed.
MAINTENANCE OPERATION RECORDS	None disclosed.

ITEM	REMARKS
SPILLWAY PLAN	No original plans were disclosed.
SECTIONS	Cross-section for this report was prepared from visual inspection.
DETAILS	
OPERATING EQUIPMENT PLANS & DETAILS	None.

BIRCHWOOD LAKE
CHECK LIST
HYDROLOGIC AND HYDRAULIC DATA
ENGINEERING DATA

DRAINAGE AREA CHARACTERISTICS: 0.2 sq. mi., hilly, wooded

ELEVATION TOP NORMAL POOL (STORAGE CAPACITY) 551.1 ft. MSL (89 ac-ft)

ELEVATION TOP FLOOD CONTROL POOL (STORAGE CAPACITY: Not applicable)

ELEVATION MAXIMUM DESIGN POOL: 553.5 ft. MSL (117)

ELEVATION TOP DAM: 552.7 ft. MSL

CREST: Stoplog section

a. Elevation 551 ft. MSL

b. Type Stoplog

c. Width 3 inches

d. Length 2 feet

e. Location Spillover South end of Reservoir

f. Number and Type of Gates None

OTHER OUTLETS: Natural emergency spillway

a. Type Natural Low Saddle

b. Location Northeast end of Reservoir

c. Invert Elevation 551.6 ft. above MSL

d. Emergency Draindown Facilities None

HYDROMETEOROLOGICAL GAGES: None

a. Type _____

b. Location _____

c. Records _____

MAXIMUM NON-DAMAGING DISCHARGE: 178 cfs

APPENDIX 2

PHOTOGRAPHS

BRICHWOOD LAKE DAM



16 MAY 1979

VIEW OF THE DAM CREST LOOKING SOUTH FROM RESERVOIR



16 MAY 1979

VIEW OF INLET TO SPILLWAY DISCHARGE PIPE

BIRCHWOOD LAKE DAM

2-1



16 MAY 1979

SPILLWAY PIPE DISCHARGING INTO COLLECTION BOX ABOUT
HALFWAY DOWN DOWNSTREAM SLOPE




16 MAY 1979

VIEW LOOKING UPSTREAM ALONG SPILLWAY DISCHARGE PIPE

BIRCHWOOD LAKE DAM

2-2



16 MAY 1979

VIEW OF BIRCHWOOD LAKE LOOKING NORTH FROM CREST



16 MAY 1979

VIEW LOOKING DOWN ON CRYSTAL LAKE FROM TOE OF DAM
AT SPILLWAY DISCHARGE PIPE

BIRCHWOOD LAKE DAM

2-3



16 MAY 1979

VIEW ACROSS THE DAM CREST LOOKING NORTH



16 MAY 1979

VIEW OF LOW SADDLE ON SOUTHEAST BANK OF RESERVOIR
NORTH OF SPILLWAY

BIRCHWOOD LAKE DAM

2-4



16 MAY 1979

VIEW OF LOW SADDLE AT NORTH END OF THE LAKE



16 MAY 1979

VIEW OF LOW SADDLE AT NORTH END OF THE LAKE VIEWED
FROM WEST BANK

BIRCHWOOD LAKE DAM

2-5



16 MAY 1979

OUTLET OF SPILLWAY DISCHARGE PIPE



16 MAY 1979

SEEPAGE AREA AT DOWNSTREAM SLOPE LOOKING TOWARD
CRYSTAL LAKE

BIRCHWOOD LAKE DAM



16 MAY 1979

RECONSTRUCTION OF STONE WALL ALONG SOUTH END OF
RESERVOIR ADJACENT TO SPILLWAY INLET



16 MAY 1979

VIEW ACROSS DOWNSTREAM SLOPE OF DAM JUST NORTH OF
SPILLWAY PIPE

BIRCHWOOD LAKE DAM

2-7

APPENDIX 3

HYDROLOGIC COMPUTATIONS

BIRCHWOOD LAKE DAM

Anderson-Nichols & Company, Inc.

Subject

HSH

Sheet No.

1

of

17

Date

Computed

Checked

FDD

JOB NO. 3290-02 BIRCHWOOD LAKE DAM

SQUARES

1/4 IN. SCALE

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 3

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

19

20

21

22

23

24

25

26

27

28

29

30

31

32

33

34

35

36

37

38

39

HYDROLOGIC COMPUTATIONS

BIRCHWOOD LAKE DAM

LOCATION : MORRIS COUNTY, N. J.

DRAINAGE AREA : 0.2 SQ. MILE

EVALUATION CRITERIA : SIZE - SMALL
HAZARD - HIGH

JOB NO. 3290-03BIRCHWOOD LAKESQUARES
1/4 IN. SCALE

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30

BIRCHWOOD LAKE - COMPUTATION OF TIME OF CONCENTRATION

	L	H	S
OVERLAND FLOW	~2300'	~150'	.0652

 T_c - TIME OF CONCENTRATION① BY KIRPICH NOMOGRAPH $T_c = 8.8$ MINUTES② BY IZZARDS FORMULA

$$T_c = \frac{L^{1.115}}{7700 H^{.28}} = \frac{2300^{1.115}}{7700 \times 150^{.28}} = 6.5 \text{ MINS}$$

③ BY EQUATION - CALIFORNIA CULVERT P. 71 DESIGN OF STORM CAN

$$T_c = \left(\frac{11.9 L^2 \text{ (MILES)}}{H \text{ (FT)}} \right)^{.385} = \left(\frac{11.9 \times .4356^3}{150} \right)^{.385} = 8.7 \text{ MINS}$$

④ WESTON FORMULA

$$T_c = \frac{L}{3600 V} = \frac{2300}{3600 \times 2.5 \text{ ft/sec}} = 15.2 \text{ MINS}$$

AVERAGE $T_c \approx 10$ MINUTES

SUBJECT: H.P.
ANDERSON - NICHOLS & CO. INC.
DATE: 08-21-79
COMPUTED BY: J.C.
CHECKED BY: P.D.

LOG # 3290-03

BIRCHWOOD LAKE DAM - X SECTION ALONG DAM CREST

535.

550.

545.

540.

535.

530.

531.11

STOP LOGS

SUBJECT: H₂O
JOB # 3290-03
DATE: 06-21-19
COMPLETED: 09
CHECKED: 523

BIRCHWOOD LAKE DAM - X-SECTION
ALONG NATURAL LOW SPOT
ON SOUTH BANK

530 -

535 -

540 -

545 -

551.11

VER. SCALE - 1" = 5'
HOR. SCALE - 1" = 20'

5.1.17

SUBJECT HIGH
 JOB # 3290-03
 DATE 06-20-79
 CONTINUED JO.

BIRCHWOOD LAKE DAM - X-SECTION ALONG NATURAL LOW SPOT
 ON NORTHEAST BANK OF THE LAKE

560. -

555. -

550. -

VER. SCALE 1"=5'
 HOR. SCALE 1"=20'

545. -



JOB NO. 3290-03

BIRCHWOOD LAKE DAM

SQUARES
1/4 IN. SCALE

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30

BIRCHWOOD LAKE DAM - RATING CURVE COMPUTATIONS

DISCHARGE THROUGH THE PIPE ONLY

(FIRST SECTION - FROM BIRCHWOOD
LAKE TO COLLECTOR BOX L=37')

$$L = 37'$$

$$S = 0.082$$

$$d = 10" \quad (.33 \text{ FT})$$

$$A = .545 \text{ SQ FT}$$

NO PRESSURE FLOW

$$Q = \frac{K'}{h} d^{8/5} S^{1/2}$$

$$n = 0.01$$

K' - FRICTION

TABLE 7-14 - 2

BRASS & KING

HANDBOOK OF HYDRAULICS

ELEV.	K'	Q [CFS]
550.3	.0585	.93
551.0	.2160	2.44
551.2	.402	6.41
551.4	.496	7.92

PRESSURE FLOW

$$Q = A \sqrt{\frac{2gh}{1+K}}$$

ELEV.	h [FT]	Q [CFS]
551.6	4.1	5.2
551.8	4.3	5.4
552.0	4.5	5.5
552.2	4.7	5.6
552.4	4.9	5.75
552.6	5.1	5.87
552.8	5.3	5.99
552.	5.5	6.09

$$K_f - \text{friction loss} \quad K_f = \frac{52.37 n^2}{d^{4.93}}$$

$$K_f = .0285$$

$$\text{FRICTION LOSS} = .0285 \times 37 = 1.05$$

$$\text{INLET LOSS} \quad K_b = 0.78$$

(FROM P. 5.5-1 CCS HYDRAULICS
HANDBOOK)

$$\Sigma K = 1.83$$

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DOD

Anderson-Nichols & Company, Inc.

Subject H.S. 4.

Sheet No. 2 of 17
 Date 05-25-77
 Computed 5.0.9
 Checked 5.0.9

JOB NO. 3290-03

SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
 1/4 IN. SCALE

BIRCHWOOD LAKE DAM - RATING CURVE
 COMP. CONTINUE

ELEV.	h	Q.
	[ft]	[cfs]
552.5	6.	6.27
554.	6.5	6.63
554.5	7.	6.88
555.	7.5	7.12
555.5	8.0	7.35
556.	8.5	7.58
556.5	9.0	7.80
557.0	9.5	8.01

FLOW OVER THE STOP LOGS WEIR ONLY

[MIN. ELEV.
 551.0 ft]

$Q = C L H^{3/2}$ $C = 3.5$ $L = 2.0'$

ELEV.	h	Q.
	[ft]	[cfs]
551.2	.2	.63
551.4	.4	1.77
551.6	.6	3.20
551.8	.8	5.0
552.0	1.0	7.0
552.2	1.2	9.2
552.5	1.5	12.8

THIS PAGE IS BEST QUALITY PRACTICABLE
 FROM COPY FURNISHED TO DDC

Anderson-Nichols & Company, Inc.

Subject HSHSheet No. 9 of 17
Date 06-25-77
Computed J.G.
Checked J.G.JOB NO. 3290-02

RICHWOOD LAKE DAM

SQUARES
1/4 IN. SCALE

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30

FLOW OVER THE TOP OF THE DAM ONLYMIN. ELEV.
552.72

$$Q = C \cdot L \cdot H^{3/2}$$

$$C = 2.8$$

ELEV. [FT]	H. [FT]	L. [FT]	Q. [CFS]
553.0	.27	~ 82.	32.2
553.5	.77	~ 97.	183.
554.0	1.27	~ 120.	460.
554.5	1.77	~ 140.	923.

FLOW OVER NATURAL LOW SPOT ON SOUTH BANK ONLYMIN. ELEV.
552.5

ELEV. [FT]	H. [FT]	L. [FT]	Q. [CFS]
551.0	.5	~ 80.	79.2
554.5	1.0	~ 100.	280.

FLOW OVER NATURAL LOW SPOT ON NORTHEAST BANK ONLYMIN. ELEV.
551.6


ELEV. [FT]	H. [FT]	L. [FT]	Q. [CFS]
552.	.4	~ 25.	17.7
552.5	.9	~ 40.	95.6
553.0	1.4	~ 55.	255.
553.5	1.9	~ 70.	513.
554.0	2.4	~ 80.	833.
554.5	2.9	~ 85.	1175.

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

10-17

NO. 3115-R, 20 DIVISIONS PER INCH (100 DIVISIONS) BY 2 3-INCH CYCLES RATIO RULING.
 IN STOCK DIRECT FROM CONY & ROCK CO., NORWOOD, MASS. 02062
 PRINTED IN U.S.A.


NO. 3115-R, 20 DIVISIONS PER INCH (100 DIVISIONS) BY 2 3-INCH CYCLES RATIO RULING.



THIS PAGE IS BEST QUALITY PRACTICABLE
 FROM COPY FURNISHED TO DDC

11 4 7

NO. 3115-R, 20 DIVISIONS PER INCH (120 DIVISIONS) BY 3-INCH CYCLES RATIO RULING.
 IN STOCK DIRECT FROM CODEX BOOK CO., NORWOOD, MASS. 02062
 PRINTED IN U.S.A.




Discontinuity

THIS PAGE IS BEST QUALITY PRACTICABLE
 FROM COPY FURNISHED TO DDC

12-17

NO. 3115 R. 20 DIVISIONS PER INCH (120 DIVISIONS) BY 2 1/2-INCH CYCLES RATIO RULING.
 IN STOCK DIRECT FROM CODEX PAPER CO., NORWOOD, MASS. 02062
 PRINTED IN U.S.A.
 CODEX PAPER



Discharge [CFS]

THIS PAGE IS BEST QUALITY PRACTICABLE
 FROM 0-1000 CFS TO 1000 CFS

Anderson-Nichols & Company, Inc.

Subject

MCH

Sheet No. 12 of 17

Date 06-25-74

Computed

Checked F.D.D.

JOB NO. 3290-03

BIRCHWOOD LAKE DAM

SQUARES
1/4 IN. SCALE

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29

BIRCHWOOD LAKE DAM - RATING CURVE COMPUTATION

SUMMARY OF DISCHARGES

ELEV.	STOP LOGS	PIPE	OVER NORTHEAST TOP OF PART OF THE THE DAM		OVER SOUTH LOW PART OF THE LAKE		TOTAL	DISCHARGE WHICH THE LOWEST LOW PART OF THE LAKE
			LAKE		LAKE		[cfs]	
551.2	.63						.63	.63
551.4	1.77						1.77	1.77
551.6	3.20						3.20	3.20
551.8	5.0						5.0	5.0
552.0		5.5	17.7				23.2	5.5
552.5		5.8	95.6				101.4	5.8
552.0		6.1	205.	22.2			227.2	6.1
553.5		6.4	513.	183.5			702.9	6.4
554.0		6.6	833.	480.	79.2		1395.3	6.6
554.5		6.9	1175.	923.	280.		2384.9	6.9


THIS PAGE IS BEST QUALITY FRAGTIGABLE
FR

DDC

14-17

NO. 31,226, 30 DIVISIONS PER INCH (120 DIVISIONS) BY FOUR CYCLES RATIO RULING.
 IN STOCK DIRECT FROM CODEX BOOK CO., NORWOOD, MASS. 02062
 PRINTED IN U.S.A.

CODER
 GRAPH PAPER



Discharge

THIS PAGE IS BEST QUALITY PRACTICABLE
 FROM COPY FURNISHED TO DDC

Anderson-Nichols & Company, Inc.

Subject H. C. H.

Sheet No. 15 of 17
 Date 11-17-77
 Computed
 Checked

JOB NO. 3290-02 BIRCHWOOD LAKE DAM

SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
 1/4 IN. SCALE

BIRCHWOOD LAKE DAM - STORAGE CALCULATION

ELEV.	AVERAGE H. [FT]	AVERAGE SURFACE [AC]	STORAGE [AC-FT]
551.1	8.	11.	88.
551.4	8.3	11.	91.3
552.	8.9	11.	97.9
552.5	9.4	11.	103.4
553.	9.9	11.2	110.9
553.5	10.4	11.2	116.5
554.	10.9	11.2	122.1
554.5	11.4	11.2	127.7

THIS PAGE IS BEST QUALITY PRACTICABLE
 FROM COPY FURNISHED TO DDC

Anderson-Nichols & Company, Inc.

Subject H.C.U.Sheet No. 16 of 17
Date 11-27-70
Computed ECN
Checked ECNJOB NO. 2290-02 - BIRCHWOOD LAKE DAMSQUARES
1/4 IN. SCALE

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30

BIRCHWOOD LAKE DAM - SUMMARY


ELEV.	H (FT) ABOVE STOP LOGS	Q (cfs) (DAM SIDE)	Q (cfs) NORTHEAST SIDE OF THE LAKE	Q TOTAL	STORAGE (AC-FT)
551.0	0.	0.	0.	0.	88.
551.2	.2	.62	0.	.62	
551.4	.4	1.77	0.	1.77	91.3
551.6	.6	3.20	0.	3.20	
551.8	.8	5.00	0.	5.0	
552.0	1.0	5.5	17.7	23.2	97.9
552.5	1.5	5.8	95.6	101.4	103.4
553.0	2.0	28.2	255.	283.2	110.9
553.5	2.5	169.9	512.	702.9	116.5
554.0	3.0	565.3	833.	1398.3	122.1
554.5	3.5	1209.9	1175.	2384.9	127.7

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

ANDERSON ENGINEERING CO. INC.
 SUBJECT: H. M.
 COMPUTED: J. C.
 CHKD: FDD


DATE: 07-31-77

BIRCHWOOD LAKE DAM JOB# 2240-03



DAM OVERTOP AT ELEVATION 552.7 FEET MSL
 WITH $Q = 156$ CFS
 \therefore DAM CAN PASS 218% of PMF

THIS PAGE IS BEST QUALITY PRACTICABLE
 FROM COPY FURNISHED TO DDC



**NATIONAL PROGRAM OF INSPECTION OF
NON-FED. DAMS**


**BIRCHWOOD LAKE DAM
BOROUGH OF MOUNTAIN LAKES
REGIONAL VICINITY MAP**

DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA

ANDERSON-NICHOLS & CO., INC.

BOSTON, MA.

SCALE IN MILES



MAP BASED ON U.S.G.S. 7.5 MINUTE QUADRANGLE
SHEETS. BOONTON, N.J., 1954, UPDATED 1970.
MORRISTOWN, N.J., 1954, UPDATED 1970.

HEC-1 OUTPUT

BIRCHWOOD LAKE DAM

ALJOP 3290-03 PIRCHWOOD LAKE DAM BOROUGH OF MOUNTAIN LAKES,N.J. NJ#25-70
APQVERTOPPING ANALYSIS ANDERSON-NICHOLS & CO. INC. COACORE,N.P.

ALJOP 3290-03 PIRCHWOOD LAKE DAM BOROUGH OF MOUNTAIN LAKES,N.J. NJ#25-70
APQVERTOPPING ANALYSIS ANDERSON-NICHOLS & CO. INC. COACORE,N.P.

A30.1, 0.25, 0.5 AND 1.0 MULTIPLES OF PMF FROM 6-HOUR PMF

18
9
5
70

10
15
20
25
30
35
40
45
50
55
60
65
70
75
80
85
90
95
100

1

W
R
I
D
E
D
E
V
E
L
O
P
I
N
F
L
O
W
H
Y
D
R
O
G
R
A
P
P
F
O
R
B
I
R
C
H
W
O
O
D
L
A
K
E
1

[illegible][illegible][illegible]

	1967	1968	1969	1970	1971	1972	1973	1974	1975	1976	1977	1978	1979	1980	1981	1982	1983	1984	1985	1986	1987	1988	1989	1990	1991	1992	1993	1994	1995	1996	1997	1998	1999	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010	2011	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041	2042	2043	2044	2045	2046	2047	2048	2049	2050	2051	2052	2053	2054	2055	2056	2057	2058	2059	2060	2061	2062	2063	2064	2065	2066	2067	2068	2069	2070	2071	2072	2073	2074	2075	2076	2077	2078	2079	2080	2081	2082	2083	2084	2085	2086	2087	2088	2089	2090	2091	2092	2093	2094	2095	2096	2097	2098	2099	2100	2101	2102	2103	2104	2105	2106	2107	2108	2109	2110	2111	2112	2113	2114	2115	2116	2117	2118	2119	2120	2121	2122	2123	2124	2125	2126	2127	2128	2129	2130	2131	2132	2133	2134	2135	2136	2137	2138	2139	2140	2141	2142	2143	2144	2145	2146	2147	2148	2149	2150	2151	2152	2153	2154	2155	2156	2157	2158	2159	2160	2161	2162	2163	2164	2165	2166	2167	2168	2169	2170	2171	2172	2173	2174	2175	2176	2177	2178	2179	2180	2181	2182	2183	2184	2185	2186	2187	2188	2189	2190	2191	2192	2193	2194	2195	2196	2197	2198	2199	2200	2201	2202	2203	2204	2205	2206	2207	2208	2209	2210	2211	2212	2213	2214	2215	2216	2217	2218	2219	2220	2221	2222	2223	2224	2225	2226	2227	2228	2229	2230	2231	2232	2233	2234	2235	2236	2237	2238	2239	2240	2241	2242	2243	2244	2245	2246	2247	2248	2249	2250	2251	2252	2253	2254	2255	2256	2257	2258	2259	2260	2261	2262	2263	2264	2265	2266	2267	2268	2269	2270	2271	2272	2273	2274	2275	2276	2277	2278	2279	2280	2281	2282	2283	2284	2285	2286	2287	2288	2289	2290	2291	2292	2293	2294	2295	2296	2297	2298	2299	2300	2301	2302	2303	2304	2305	2306	2307	2308	2309	2310	2311	2312	2313	2314	2315	2316	2317	2318	2319	2320	2321	2322	2323	2324	2325	2326	2327	2328	2329	2330	2331	2332	2333	2334	2335	2336	2337	2338	2339	2340	2341	2342	2343	2344	2345	2346	2347	2348	2349	2350	2351	2352	2353	2354	2355	2356	2357	2358	2359	2360	2361	2362	2363	2364	2365	2366	2367	2368	2369	2370	2371	2372	2373	2374	2375	2376	2377	2378	2379	2380	2381	2382	2383	2384	2385	2386	2387	2388	2389	2390	2391	2392	2393	2394	2395	2396	2397	2398	2399	2400	2401	2402	2403	2404	2405	2406	2407	2408	2409	2410	2411	2412	2413	2414	2415	2416	2417	2418	2419	2
--	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	------	---

01	.298	.296	.299	.296	.298	.291
01	.234	.234	.234	.234	.234	.234

01	.234	.
01	.234	.

22 13

13-3-1

K10VERTOPPING ANALYSIS

Y	1	
Y	1	
Y		-551.1
Y		-1

Year	1951.0	1951.2	1951.4	1951.6	1951.8	1952.	1952.5	1953.	1953.5
Y4	551.0	551.2	551.4	551.6	551.8	552.	552.5	553.	553.5

[illegible]

Y5	2385	00
01	2	00
02	0	00
03	4	00
04	0	00
05	5	00
06	1	00
07	2	00

88	91.3	97.9	103.4	110.9	116.3	122.1	121.7
38							
1E	551.0	551.4	552.	552.5	553.	553.5	554.5

90 552 7
98 551.0

20 552.1
K 99

PREVIEW OF SEQUENCE OF STREAM NETWORK CALCULATIONS

BIENCE HYDROGRAPH AT

ROUTE HYDROGRAPH TO
A1
A2

END OF NETWORK

PREVIEW OF SEQUENCE OF STREAM NETWORK CALCULATIONS

RUNOFF HYDROGRAPH AT
ROUTE HYDROGRAPH TO
END OF NETWORK

A1 A2

.....
 FLOOD HYDROGRAPH PACKAGE (HEC-1)
 DAM SAFETY VERSION JULY 1978
 LAST MODIFICATION 26 FEB 79

PUN DATE: 79/07/26.
 TIME: 19.55.11.

JCP 3290-03 BIRCHWOOD LAKE DAM BOROUGH OF MOUNTAIN LAKES, N.J. NJ#25-70
 OVERTOPPING ANALYSIS ANDERSON-NICHOLS & CO. INC. CONCORD, N.H.
 0.1, 0.25, 0.5 AND 1.0 MULTIPLES OF PMF FROM 6-HOUR PMF

JCP SPECIFICATION									
NQ	NHR	NMIN	IDAY	IHP	IMIN	METRC	IPLT	IPRT	ASTAN
99	0	5	0	0	0	0	0	0	0
JOPER				NWT	LROPT	TRACE			
				5	0	0			

MULTI-PLAN ANALYSES TO BE PERFORMED
 NPLAN= 1 NRTIO= 4 LRTIO= 1
 RTIOS= .10 .25 .50 1.00

.....

SUB-AREA RUNOFF COMPUTATION

DEVELOP INFLOW HYDROGRAPH FOR BIRCHWOOD LAKE

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRY	INAME	ISTAGE	IAUTO
A1	0	0	0	0	1	1	0	0

HYDROGRAPH DATA

INHYD	IUNG	TAREA	SNAP	TRSDA	TPSPC	RATIO	ISNOW	ISAME	LOCAL
0	2	.20	0.00	.20	.80	0.000	0	1	0

PRECIP DATA		PRECIP PATTERN	
MP	STCRM	DAJ	DAK
72	0.00	0.00	0.00

.21	.21	.21	.21	.21	.21	.21	.21	.21	.21
.21	.21	.21	.21	.21	.21	.21	.21	.21	.21
.26	.26	.26	.26	.26	.26	.26	.26	.26	.26
.32	.32	.32	.32	.32	.32	.32	.32	.32	.32
.32	.32	.32	.32	.32	.32	.32	.32	.32	.32
.68	1.65	2.71	1.07	.68	.59	.39	.39	.30	.30
.30	.30	.30	.30	.30	.30	.30	.30	.30	.30
.23	.23	.23	.23	.23	.23	.23	.23	.23	.23
.23	.23	.23	.23	.23	.23	.23	.23	.23	.23

LOSS DATA

LROPT	STKR	DLTKR	RTIOL	ERAIN	STRKS	RTIOK	STRIL	CNSTL	ALSMX	RTIMP
0	0.00	0.00	1.00	0.00	0.00	1.00	1.00	.10	0.00	0.00

UNIT HYDROGRAPH DATA

TC= 0.00 LAG= .13

RECESSION DATA
STRIC= -3.00 GRCSN= 0.00 RTICR= 1.00

TIME INCREMENT TCO LARGE--(NMG IS GT LAG/2)

UNIT HYDROGRAPH 10 END OF PERIOD ORIGINATES, TCE 0.00 HOURS, LAG= 8. .13 VOL= 1.00 1.
253. 565. 410. 175. 80. 37. 16. 4.

MG.DA	MR.MN	PERIOD	RAIN	EXCS	LOSS	END-OF-PERIOD FLCL	MC.DA	MR.MN	PERIOD	RAIN	EXCS	LCSS	COMP Q
1.01	.05	1	.17	0.00	.17	1.	1.01	3.50	46	.46	.46	.01	1278.
1.01	.10	2	.17	0.00	.17	1.	1.01	3.55	47	.31	.30	.01	936.
1.01	.15	3	.17	0.00	.17	1.	1.01	4.00	48	.31	.30	.01	703.
1.01	.20	4	.17	0.00	.17	1.	1.01	4.05	49	.24	.23	.01	555.
1.01	.25	5	.17	0.00	.17	1.	1.01	4.10	50	.24	.23	.01	457.
1.01	.30	6	.17	.02	.15	6.	1.01	4.15	51	.24	.23	.01	401.
1.01	.35	7	.17	.16	.01	54.	1.01	4.20	52	.24	.23	.01	375.
1.01	.40	8	.17	.16	.01	142.	1.01	4.25	53	.24	.23	.01	364.
1.01	.45	9	.17	.16	.01	203.	1.01	4.30	54	.24	.23	.01	360.
1.01	.50	10	.17	.16	.01	230.	1.01	4.35	55	.24	.23	.01	358.
1.01	.55	11	.17	.16	.01	242.	1.01	4.40	56	.24	.23	.01	357.
1.01	1.00	12	.17	.16	.01	247.	1.01	4.45	57	.24	.23	.01	357.
1.01	1.05	13	.20	.20	.01	256.	1.01	4.50	58	.24	.23	.01	357.
1.01	1.10	14	.20	.20	.01	278.	1.01	4.55	59	.24	.23	.01	357.
1.01	1.15	15	.20	.20	.01	293.	1.01	5.00	60	.24	.23	.01	357.
1.01	1.20	16	.20	.20	.01	299.	1.01	5.05	61	.19	.18	.01	344.
1.01	1.25	17	.20	.20	.01	301.	1.01	5.10	62	.19	.18	.01	315.
1.01	1.30	18	.20	.20	.01	303.	1.01	5.15	63	.19	.18	.01	294.
1.01	1.35	19	.20	.20	.01	303.	1.01	5.20	64	.19	.18	.01	265.
1.01	1.40	20	.20	.20	.01	303.	1.01	5.25	65	.19	.18	.01	281.
1.01	1.45	21	.20	.20	.01	303.	1.01	5.30	66	.19	.18	.01	279.
1.01	1.50	22	.20	.20	.01	303.	1.01	5.35	67	.19	.18	.01	278.
1.01	1.55	23	.20	.20	.01	303.	1.01	5.40	68	.19	.18	.01	278.
1.01	2.00	24	.20	.20	.01	303.	1.01	5.45	69	.19	.18	.01	278.
1.01	2.05	25	.26	.25	.01	316.	1.01	5.50	70	.19	.18	.01	277.
1.01	2.10	26	.26	.25	.01	345.	1.01	5.55	71	.19	.18	.01	277.
1.01	2.15	27	.26	.25	.01	356.	1.01	6.00	72	.19	.18	.01	277.
1.01	2.20	28	.26	.25	.01	375.	1.01	6.05	73	0.00	0.00	0.00	232.
1.01	2.25	29	.26	.25	.01	379.	1.01	6.10	74	0.00	0.00	0.00	131.
1.01	2.30	30	.26	.25	.01	381.	1.01	6.15	75	0.00	0.00	0.00	58.
1.01	2.35	31	.26	.25	.01	382.	1.01	6.20	76	0.00	0.00	0.00	27.
1.01	2.40	32	.26	.25	.01	383.	1.01	6.25	77	0.00	0.00	0.00	12.
1.01	2.45	33	.26	.25	.01	383.	1.01	6.30	78	0.00	0.00	0.00	6.
1.01	2.50	34	.26	.25	.01	383.	1.01	6.35	79	0.00	0.00	0.00	3.
1.01	2.55	35	.26	.25	.01	383.	1.01	6.40	80	0.00	0.00	0.00	1.
1.01	3.00	36	.26	.25	.01	383.	1.01	6.45	81	0.00	0.00	0.00	1.
1.01	3.05	37	.16	.15	.01	357.	1.01	6.50	82	0.00	0.00	0.00	1.
1.01	3.10	38	.31	.30	.01	380.	1.01	6.55	83	0.00	0.00	0.00	1.
1.01	3.15	39	.31	.30	.01	387.	1.01	7.00	84	0.00	0.00	0.00	1.
1.01	3.20	40	.46	.46	.01	472.	1.01	7.05	85	0.00	0.00	0.00	1.
1.01	3.25	41	.53	.53	.01	598.	1.01	7.10	86	0.00	0.00	0.00	1.
1.01	3.30	42	1.32	1.31	.01	910.	1.01	7.15	87	0.00	0.00	0.00	1.
1.01	3.35	43	2.17	2.16	.01	1626.	1.01	7.20	88	0.00	0.00	0.00	1.
1.01	3.40	44	.85	.84	.01	2120.	1.01	7.25	89	0.00	0.00	0.00	1.
1.01	3.45	45	.54	.53	.01	1796.	1.01	7.30	90	0.00	0.00	0.00	1.

SUM 20.41 18.86 1.55 29259.
(519.)(479.)(39.)(828.52)

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL	VOLUME
CS	21.0	4.6	3.6	33.	20.3	254.
CS	60.	11.	9.	9.	828.	828.
INCH		18.69	18.90	18.90	18.90	480.00
AC-FT		479.70	480.00	480.00	480.00	201.
THOUS CU M		2.01	2.01	2.01	2.01	249.
		2.48	2.49	2.49		

[illegible]

STATION A2, PLAN 1, RATIO 3
END-OF-PERIOD HYDROGRAPH ORDINATES

OUTFLOW		STORAGE		STAGE	
0.	0.	0.	0.	0.	0.
2.	4.	4.	7.	15.	1.
5.	7.	7.	9.	15.	34.
10.	15.	15.	102.	115.	127.
15.	22.	22.	172.	174.	137.
20.	34.	34.	231.	222.	176.
25.	45.	45.	241.	186.	182.
30.	55.	55.	160.	95.	376.
35.	65.	65.	40.	37.	204.
40.	72.	72.			154.
45.	78.	78.			72.
50.	84.	84.			28.
55.	89.	89.			
60.	91.	91.			
65.	92.	92.			
70.	93.	93.			
75.	94.	94.			
80.	95.	95.			
85.	96.	96.			
90.	97.	97.			
95.	98.	98.			
100.	99.	99.			
105.	100.	100.			
110.	101.	101.			
115.	102.	102.			
120.	103.	103.			
125.	104.	104.			
130.	105.	105.			
135.	106.	106.			
140.	107.	107.			
145.	108.	108.			
150.	109.	109.			
155.	110.	110.			
160.	111.	111.			
165.	112.	112.			
170.	113.	113.			
175.	114.	114.			
180.	115.	115.			
185.	116.	116.			
190.	117.	117.			
195.	118.	118.			
200.	119.	119.			
205.	120.	120.			
210.	121.	121.			
215.	122.	122.			
220.	123.	123.			
225.	124.	124.			
230.	125.	125.			
235.	126.	126.			
240.	127.	127.			
245.	128.	128.			
250.	129.	129.			
255.	130.	130.			
260.	131.	131.			
265.	132.	132.			
270.	133.	133.			
275.	134.	134.			
280.	135.	135.			
285.	136.	136.			
290.	137.	137.			
295.	138.	138.			
300.	139.	139.			
305.	140.	140.			
310.	141.	141.			
315.	142.	142.			
320.	143.	143.			
325.	144.	144.			
330.	145.	145.			
335.	146.	146.			
340.	147.	147.			
345.	148.	148.			
350.	149.	149.			
355.	150.	150.			
360.	151.	151.			
365.	152.	152.			
370.	153.	153.			
375.	154.	154.			
380.	155.	155.			
385.	156.	156.			
390.	157.	157.			
395.	158.	158.			
400.	159.	159.			
405.	160.	160.			
410.	161.	161.			
415.	162.	162.			
420.	163.	163.			
425.	164.	164.			
430.	165.	165.			
435.	166.	166.			
440.	167.	167.			
445.	168.	168.			
450.	169.	169.			
455.	170.	170.			
460.	171.	171.			
465.	172.	172.			
470.	173.	173.			
475.	174.	174.			
480.	175.	175.			
485.	176.	176.			
490.	177.	177.			
495.	178.	178.			
500.	179.	179.			
505.	180.	180.			
510.	181.	181.			
515.	182.	182.			
520.	183.	183.			
525.	184.	184.			
530.	185.	185.			
535.	186.	186.			
540.	187.	187.			
545.	188.	188.			
550.	189.	189.			
555.	190.	190.			
560.	191.	191.			
565.	192.	192.			
570.	193.	193.			
575.	194.	194.			
580.	195.	195.			
585.	196.	196.			
590.	197.	197.			
595.	198.	198.			
600.	199.	199.			
605.	200.	200.			
610.	201.	201.			
615.	202.	202.			
620.	203.	203.			
625.	204.	204.			
630.	205.	205.			
635.	206.	206.			
640.	207.	207.			
645.	208.	208.			
650.	209.	209.			
655.	210.	210.			
660.	211.	211.			
665.	212.	212.			
670.	213.	213.			
675.	214.	214.			
680.	215.	215.			
685.	216.	216.			
690.	217.	217.			
695.	218.	218.			
700.	219.	219.			
705.	220.	220.			
710.	221.	221.			
715.	222.	222.			
720.	223.	223.			
725.	224.	224.			
730.	225.	225.			
735.	226.	226.			
740.	227.	227.			
745.	228.	228.			
750.	229.	229.			
755.	230.	230.			
760.	231.	231.			
765.	232.	232.			
770.	233.	233.			
775.	234.	234.			
780.	235.	235.			
785.	236.	236.			
790.	237.	237.			
795.	238.	238.			
800.	239.	239.			
805.	240.	240.			
810.	241.	241.			
815.	242.	242.			
820.	243.	243.			
825.	244.	244.			
830.	245.	245.			
835.	246.	246.			
840.	247.	247.			
845.	248.	248.			
850.	249.	249.			
855.	250.	250.			
860.	251.	251.			
865.	252.	252.			
870.	253.	253.			
875.	254.	254.			
880.	255.	255.			
885.	256.	256.			
890.	257.	257.			
895.	258.	258.			
900.	259.	259.			
905.	260.	260.			
910.	261.	261.			
915.	262.	262.			
920.	263.	263.			
925.	264.	264.			
930.	265.	265.			
935.	266.	266.			
940.	267.	267.			
945.	268.	268.			
950.	269.	269.			
955.	270.	270.			
960.	271.	271.			
965.	272.	272.			
970.	273.	273.			
975.	274.	274.			
980.	275.	275.			
985.	276.	276.			
990.	277.	277.			
995.	278.	278.			
1000.	279.	279.			

PEAK OUTFLOW IS 753. AT TIME 3.83 HOURS

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
753.	184.	148.	148.	13277.
21.	5.	4.	4.	376.
	8.54	8.58	8.58	8.58
	216.99	217.85	217.85	217.85
	91.	91.	91.	91.
	112.	113.	113.	113.

CFS
CMS
INCHES
MM
AC-FT
THOUS CU M

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO FLOWS			
				RATIO 1	RATIO 2	RATIO 3	RATIO 4
				.10	.25	.50	1.00
HYDROGRAPH AT	A1	.20	1	212.	530.	1060.	2120.
	(.52)	(6.00)	15.61)	30.62)	60.04)
ROUTED TO	A2	.20	1	60.	255.	753.	1850.
	(.52)	(1.70)	7.22)	21.33)	52.39)

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1									
RATIO OF Pmc	MAXIMUM RESERVOIR W.S.-ELEV	ELEVATION STORAGE OUTFLOW	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS	TOP OF DAM
.10	552.24		0.00	103.	60.	0.00	4.08	0.00	552.70
.25	552.50		.20	109.	255.	.67	3.52	0.00	106.
.50	553.54		.84	117.	753.	2.08	3.43	0.00	178.
1.00	554.23		1.53	125.	1850.	4.75	3.75	0.00	

APPENDIX 4

REFERENCE

BIRCHWOOD LAKE DAM

APPENDIX 4

REFERENCES

BIRCHWOOD LAKE DAM

1. U.S. Army Corps of Engineers, Hydrologic Engineering Center, "Flood Hydrograph Package (HEC-1) for Dam Safety Inspections - Users Manual", Davis, California, September 1978.
2. Brater, Ernest F. and King, Horace, Handbook of Hydraulics, Sixth Edition, McGraw-Hill, New York, 1976.
3. U.S. Bureau of Public Roads, "Design Charts for Open Channel Flow", October 1960.
4. Reference Data, Dams in New Jersey, No. 25-70 from NJDEP files, dated November 7, 1928.